

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


CRAWFORD COUNTY
T 28 N R 3 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 20-29

CORNER MONUMENT Set Department Monument below road surface

DATE MONUMENT PLACED AND WITNESSED 6-19-70

WITNESSES TO CORNER.....



8" H. Maple N 27 E 53.1'

8" Tw. H. Maple S 23 E 40.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a retracement in this township. Set corner from probable Newman witnesses, as recorded in early 1900 survey. Two stumps in place and possible evidence of stake remains. Also falls in line with fence North and 33' S. of fence corner.

SURVEYOR'S SEAL

SIGNED *Timothy J. Stelling* DATE 7-7-70
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68