

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

CRAWFORD COUNTY


T 28 N R 3 W

DESCRIPTION OF CORNER Sec. corner common to Sections 19-20-29-30

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 6-19-70

WITNESSES TO CORNER..... 8" S. Maple N 75 W 53.8'



\* 6" S. Maple S 46 E 46.4'

\* MSHD Witness

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a retracement in this township. Found steel fence post at corner, as established by M.S.H.D. during surveys for I-75. Unable to locate Houghton tile of record. Corner possibly should be somewhat North, by measurement, but decided not to disturb equities based on found corner without conclusive evidence.

SURVEYOR'S SEAL

SIGNED

*Leanne R. Pettig*  
REGISTERED LAND SURVEYOR 10068

DATE

7-7-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68