

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


CRAWFORD COUNTY
T 28 N R 3 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 8 - 17

CORNER MONUMENT Department Monument

DATE MONUMENT PLACED AND WITNESSED 6-19-70

WITNESSES TO CORNER.....



32" W.P. Stump S 65 E 16.3'

10" Maple S 22 W 61.4'

AND

1/2" Re-Rod N 13 E 27.7'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, and in conformity with the U.S. record for alignment, during a survey in this area.

A 1/2" iron bar was apparently established in a survey of the SW 1/4 without sufficient information on section control, and was disregarded in favor of a proportionate restoration. No U.S. evidence.

SURVEYOR'S SEAL

SIGNED

Vernon H. Ketting
REGISTERED LAND SURVEYOR 10068

DATE 7-17-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68