

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


CRAWFORD COUNTY
T 28 N R 3 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 2-3

CORNER MONUMENT Set Dept Monument

DATE MONUMENT PLACED AND WITNESSED 6-17-70

WITNESSES TO CORNER..... 8" H. Maple East 36.2'



8" H. Maple N 13 W 58.0'

Fence Corner West 33.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a survey in this township. Set corner 33' from fence corner, West and South, and at proportionate measurement for latitude, which falls nearly in line with fence West.

Unable to locate a previous corner, but believe this point probably represents Newman position as established in early 1900 survey. Best available evidence.

SURVEYOR'S SEAL

SIGNED *Timothy A. Selby* DATE 7-7-70
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68