

MAR 29 2000

LIBER

4

PAGE

54

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 28N R 4W E-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

13 DEC 99 9:48 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1856 W. Warner, DS July 31, 1933 H.L. Botsford #1647 L1, P59 & L2, P127 LCRC Nov 29, 1973 K. Ostling #10068
 Mon - Old gr. Sec. Cor. Reestablished Mon - Reestablished by Dbl. Proportionate Restored Corner according to previous surveys of record.
 Wit: 8" Beech S41°E 14 lks. Mon - DNR Mon. Wit: 8" Maple (in clump) N44°E 31.0
 6" Beech N65°W 45 lks. 36" W. P. Stub S58°W 35.4
 13" W. P. Stp. N30°W 6.0
- L150, P183 Jan 13, 1975 N. Parker #16939 L163, P193 Aug 8, 1977 N. Parker #16939
 L152, P48 Mar. 31, 1975 N. Parker #16939 Mon - DNR Monument
 Mon - DNR Monument Wit: 8" Maple N39°W 49.9
 10" Maple S24°W 30.26
 Fence cor. Post S10°W 25.75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe DNR cap broken off 9± S. of Centerline of E-W road; found 8" Beech S25°W 30.2; found Stump N39°W 49.9; found Fence cor. post S15°W 26.15A
Accepted 1" pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon: Standard Crawford County Monument.
 Wit: Spike in W. face of fence post N03°W 39.02
 Spike in West side 18" R. Oak S58°W 45.84
 Spike in West side of fence post S15°W 26.15
 Spike in East side S25°W 30.69

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE NOV 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers*

Date 12-03-1999

Surveyor's Michigan License No. 31600