

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 28N R 4W E-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
28 DEC 99 3:01 P.M.
SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

LIBER 4 PAGE 64

I, Marvin E. Myers, in a field survey on July 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1866 W. Warner, DS L1, P64 LCRC Nov 6, 1973 K. Ostling #10068 L150, P183 Jan 13, 1975 N. Parker #16939
- Mon - Old gr. Sec. Cor. Reestablished Mon - Set by Proportionate Measure DNR Mon. L152, P48 Mar. 31, 1975 N. Parker #16939
- Wit: 9" Beech N49°E 18 lks. Wit: 7" H. Maple S13°W 23.75 Mon - MDNR Mon.
- 8" Beech S30°W 23 lks. 8" H. Maple S80°E 19.4
- L273, P585 1985 C. Robinson #16390
- Mon - DNR Monument
- Wit: 8" Y. Birch N27°E 34.97
- 14" B. Cherry S38°E 31.98
- 8" Tw. B. Cherry S62°W 31.16
- 9" Maple N20°W 8.60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument with RedTop Post along side; found 8" Spike in N. side 13" Maple N66°W 11.27; found 7" (now 12") H. Maple S13°W 23.75; found 8" (now 13") 8" H. Maple S80°E 19.4 Accepted DNR monument as a reestablishment of the position of the Original Government Corner. Left DNR monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon - DNR monument left in place
- Wit: Nail and tag in East side 7" Beech N02°E 26.50
- Spike South side 13" Maple S76°E 19.71
- Spike West side 12" Maple S16°W 24.14
- Spike in North side 13" Maple N66°W 11.27



CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Nov 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date 12-06-1999