

MAR 29 2000

LIBER

4

PAGE

55

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

For corners in

Crawford

(County)

Located In:

Corner Code #

13 DEC 99 9:49 A.M.

SANDRA MOORE
REGISTER OF DEEDS

1. Public Land Survey

T 28N R 4W

F-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on July 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7						8			9		10	11
5													
6	18						17			16		15	14
7													
8	19						20			21		22	23
9													
10	30						29			28		27	26
11													
12	31						32			33		34	35
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1856 W. Warner, DS
Mon - Old gr. Sec. Cor. Reestablished
Wit: 5" Beech S88°W 14 lks.
9" Beech N30°W 24 lks.

P147 Co. Survey Jun 26 1932 Ed Houghton #1122
Mon - Set CT Post for 1/4 corner
North 19 feet

P20 Co. Survey records July 31, 1933 H.L. Botsford #1647
Mon - found Stake in center of road by Houghton and 2 NBT's
Wit: Conc. Mon North 33.00

LCRC L1, P63 Nov 6, 1973
K. Ostling # 10068
Fd. 2x2 wood stake 33' S. of
Conc. Filled Tile.
Mon - Set DNR Monument
Wit: Conc. Filled tile N. 33.00
13" Maple S17°E 26.6
14" Maple S66°W 57.7
1/2" Sq. Iron S. 32.8

L150, P183 Jan 13, 1975 N. Parker # 16939
Mon - MDNR Mon.

LCRC L2, P243 June 26, 1981 G.F. DeLamater #13030
Mon - Fd 1" bar
Wit: 16" Maple S17°E 26.90
SW cor. garage Fnd. N62°W 104.55
Power Pole N75°E 89.00

L273, P505 1987 C I Robinson #16390
Mon - DNR Mon top broken
Wit: Conc. Filled Tile North 33.70
13" Maple S17°E 26.60
1/2" Sq. Iron South 32.74
16" Maple S60°E 54.70

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument (1" pipe with top broken off) 1± South of E-W road; found 20" Maple Stump S17°E 26.90; found SW cor. garage foundation N62°W 104.55; Accepted DNR Monument as the best available evidence of the position of the Original Corner. Replaced pipe with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate location of original corner:

Mon - Standard Crawford County Monument
Wit: Spike in East side 4" Spruce N05°E 37.92
Spike in NE side 8" Beech S50°E 81.75
1/2" Square bar S02°W 23.01
SW corner of Garage Foundation N62°W 104.55

CRAWFORD COUNTY

PEER GROUP APPROVAL

DATE NOV 30, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31500

Date Dec 6, 1999

