

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4 PAGE 57

For corners in SECTION

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28NR 4W</u>	<u>F-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property In Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
13 DEC 99 9:49 A.M.
SANDRA HOORE
Register of Deeds Stamp & File
Number

I, Marvin E. Myers, in a field survey on July 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11 = 1/4 Cor. common to Sec. 28 & 33, T28N, R4W
G.L.O. 1856 Walter Warner, DS
Mon: Reestablished old qr Sec Post
Wit: 8" Hemlock S20°W 25 lks
5" Beech N22°E 16 lks

1973 LCRC L. 1, P. 63 K.J. Ostling #10068
Mon - Set DNR Monument by proportionate measurement
Wit: 16" W. Pine S20°W 132.9'
4" B. Cherry S20°E 12.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 = 1/4 Cor. common to Sec. 28 & 33, T28N, R4W
Mon - Found DNR Monument
Wit: Found 16" W. Pine S20°W 132.9'
Found 4" B. Cherry S20°E 12.5'

Accepted DNR monument as a careful and faithful reestablishment of the position of the Original Government corner.
Left DNR Monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 = 1/4 Cor. common to Sec. 28 & 33, T28N, R4W
Mon - DNR Monument 1" Pipe with Brass Cap.
Wit: Spike in E. side 10" R. Pine N03°W 6.41'
Spike in N. side 12" R. Pine S70°W 4.64'
Spike in N. side 8" R. Pine S40°E 7.26'
Spike in N. side 6" R. Pine S80°E 7.69'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Nov 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers* Date Dec 6, 1999
Surveyor's Michigan License No. 31600