

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Crawford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 28N R 4W G-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
13 DEC 99 9:48 A.M.
SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER 4 PAGE 53

I, Marvin E. Myers, in a field survey on July 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. - 1856 W. Warner, DS L1, P83 Sept 1971 N. Parker, PS #16939 L1, P63 LCRC Nov 6, 1973 K. Ostling #10068
- Mon - Old gr. Sec. Cor. Reestablished Position calculated. Mon - Fd 1 1/2" Pipe as est. in previous local survey
- Wit: 5" Beech N22°E 9 lks. Set DNR Monument.
- 6" Beech S50°W 9 lks. Wit: 8" Y. Birch N27°E 34.7
- L273, P585 1985 C. Robinson #16390 14" B. Cherry S38°E 31.5
- Mon - DNR Monument
- Wit: 8" Y. Birch N27°E 34.97
- 14" B. Cherry S38°E 31.98
- 8" Tw. B. Cherry S62°W 31.16
- 9" Maple N20°W 8.60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument; found 8" Y. Birch Stump N27°E 34.7; found 14" B. Cherry S38°E 31.5; found 8" Tw. B. Cherry S62°W 31.16; 9" Maple N20°W 8.60 Accepted DNR Monument as the best available evidence of the position of the Original Corner. Left DNR Monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon - DNR Monument
- Wit: Spike in Northeast side 10' Maple S84°E 15.50
- 9" Maple N20°W 8.62
- 8" Tw. B. Cherry S62°W 31.16
- 14" B. Cherry S38°E 31.45



CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE NOV 30, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date 12-03-1999