

**SURVEY & REMONUMENTATION**

APR 07 1998

**SURVEY & SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER**

**3**

**PAGE 312**

For corners in

Crawford  
(County)

Located In:

Corner Code #

1. Public Land Survey

T28N R4W  
T27N R4W  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

✓ I-13  
I-I

2. Property Controlling in Section  
3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

5 JAN 98 10:37 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James L. Schwandt, in a field survey on 10-13, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |   |   |   |
|---|---|---|
| I-13 T28N-R4W<br>G.L.O. W. Warner, 1856<br>Set Post<br>18" Hemlock N35°W, 12 Links<br>12" Hemlock N36°E, 11 Links | A. E. Newman, 1903<br>Sunk T RR Iron 2' Long for Cor<br><br>G. D. Henning, 1977<br>1/2" Bar<br>10" Poplar S35°E, 98.4'<br>12" Maple N29°E, 89.4'<br>6" Maple N41°W, 68.9' | N.F. Parker, 1982<br>1/2" Bar<br>8" Poplar S35°E, 98.4'<br>8" Maple N29°E, 89.4'<br>8" Maple N41°W, 68.9' |
| A.E. Newman, 1901<br>10" Tamarack S60°W, 30 Links<br>11" Cedar S21°E, 13 Links                                    |   |   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fnd. Bent 1/2" Bar
- Fnd. Nail 12" Maple N29°E, 89.45'
- Fnd. Nail 12" Maple N41°W, 69.00' Overgrown & Badly Bent

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
DATE OCT 16, 1997

*Marvin E. Myers P.S.*  
**Marvin E. Myers, P.S.**  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced 1/2" bar with C.C.M.
- C.C.M. is accepted as a careful and faithful perpetuation of the position of the original corner.
- Set Spk. PP N65°W, 95.60'
- Set Spk. PP S70°W, 105.47'
- Set Spk. 10" Twin Aspen S40°E, 74.55'
- Fnd. Nail 12" Maple N29°E, 89.45'
- Fnd. Nail 12" Maple N41°W, 69.00'



Signed by James L. Schwandt  
Surveyor's Michigan License No. \_\_\_\_\_  
26466

Date 12-15-97