

APR 29 1999

LIBER

3 PAGE 351

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford

(County)

Located In:

Corner Code #

- 1. Public Land Survey T28N R4W K-11  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

31 DEC 98 9:40 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, James L. Schwandt, in a field survey on 10/15, 1998 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) K-11, T28N-R4W; G.L.O. W. Warner, 1857; Set Post; Aspen 10", S63°W, 24 links; Aspen 10", S45°W, 37 links.
- 2.) A.E. Newman, 1901; Set corner; Yellow Pine 15", S65°W, .30 links.
- 3.) Henning, 1951; Found 1/2" bar and wood post for section corner evidently set by surveys in Section 35.
- 4.) Kenneth J. Ostling, #10068, 1972; Found 5/8" rerod from 1948, G.F. Delamater survey (Note: could not find a copy of Delamater survey); Set DNR monument; 20" White Pine, N32°W, 46.6'; 16" White Pine, N62°E, 41.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- 1.) Found DNR Monument at corner; Found blaze, 24.0" White Pine, N32°W, 47.41'; Found Blaze, 20.0" White Pine, N62°E, 42.0'.

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Aug 21, 1998

*Marvin E. Myers, P.S.*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon: DNR Monument left in place, accepted as the best available evidence of the position of the original corner.
- Wit: Set spike and blaze, Twin 6.0" Maple, N64°W, 28.67'
- Set spike and blaze, 24.0" White Pine, N32°W, 47.41'
- Set spike and blaze, 6.0" Maple, N57°E, 7.57'
- Set spike and blaze, 20.0" White Pine, N62°E, 42.00'



Signed by James L. Schwandt  
Surveyor's Michigan License No. 26466

10-15-98