

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code **LIBER**

3 PAGE 308

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

5 JAN 98 10:36 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T28N R4W	K-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James L. Schwandt, in a field survey on 10-13, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-12 T28N-R4W
G.L.O. W. Warner, 1856
Post
6" Aspen S45°E, 32 Links
6" Aspen S16°W, 32 Links

A. E. Newman, 1901
Set 1/4 Post
28" W. Pine Stump S36°E, 70 Links

G.R. Ender, 1948
Conc. Mon. For Plat
of Hartig Pines

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. Conc. Mon.
Fnd. Remains 28" W. Pine Stump S36°E, 55.44'
Fnd. Spk. West side 6" Maple N35°E, 19.19'
Fnd. Spk. North side 8" Pine S60°E, 17.17'
Fnd. Spk. North side 5" Pine West, 23.56'
Fnd. Spk. East side 20" Pine N30°W, 26.05'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE 0016, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced Conc. Mon. With C.C.M.
C.C.M is accepted as a careful and faithful perpetuation of the position of the original corner.

Fnd. Remains 28" W. Pine Stump S36°E, 55.44'
Fnd. Spk. West side 6" Maple N35°E, 19.19'
Fnd. Spk. North side 8" Pine S60°E, 17.17'
Fnd. Spk. North side 5" Pine West, 23.56'
Fnd. Spk. East side 20" Pine N30°W, 26.05'



Signed by James L. Schwandt
Surveyor's Michigan License No. 26466

Date 12-15-97