

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located in:

Corner Code #

1. Public Land Survey

T28N R4W

LIBER
K-13
K-1

3

PAGE 309

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

5 JAN 98 10:36 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, James L. Schwandt, in a field survey on 10-13, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 T28N-R4W
G.L.O. W. Warner, 1856
Set Post
8" Beech N68°W, 22 Links
4" Aspen N30°E, 17 Links

A. E. Newman, 1901
Set Corner
35" W. Pine Stump N11°W, 39 Links

Kenneth J. Ostling #10068
Set Dnr. Mon.
6" W. Pine S02°E, 81.50'
3" W. Pine N53°E, 21.70'
18" R. Pine N37°W, 96.90'
26" W. Pine Stump N08°W, 26.30'

G.D. Henning #2240, 1976
Fnd DNR Mon of Record

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. DNR Mon. in Cor.
Fnd. Spk. 7" Maple N50°W, 18.42'
Fnd. Spk. 4" Pine N55°E, 21.72'
Fnd. Spk. 5" Aspen S35°E, 19.92'
Fnd Spk. 4" Maple S20°W, 33.78'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE OCT 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Fnd. Dnr. Mon. In Cor.
Dnr. Mon. Is accepted as a careful and faithful perpetuation of the position of the original corner.

Fnd. Spk. 7" Maple N50°W, 18.42'
Fnd. Spk. 4" Pine N55°E, 21.72'
Fnd. Spk. 5" Aspen S35°E, 19.92'
Fnd Spk. 4" Maple S20°W, 33.78'



Signed by James L. Schwandt
Surveyor's Michigan License No. _____
26466

Date 12-15-97