

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


CRAWFORD COUNTY
T 28 N R 4 W

DESCRIPTION OF CORNER S 1/4 corner, Section 26

CORNER MONUMENT 5/8" Iron Bar

DATE MONUMENT PLACED AND WITNESSED 5-25-72

WITNESSES TO CORNER.....



6" W. Pine N 30 E 63.4'

6" Balsam N 18 W 77.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Left 5/8" iron bar in place, as established by unknown, but probably Newman or Houghton. Appears to have been used in subdivision of Sec. 35, and a later survey in the SW 1/4 of Sec. 26, although Henning 1950 survey used a theoretical midpoint some 21' West of pipe. Feel the iron is best evidence of proper position for this corner.



SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR 10068

DATE

5-31-72

DISTRIBUTION:

Forestry Division, Lansing