

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

CRAWFORD COUNTY


T 28 N R 4 W

DESCRIPTION OF CORNER 1/4 corner between 26-23

CORNER MONUMENT Set DNR Monument

DATE MONUMENT PLACED AND WITNESSED 5-25-72

WITNESSES TO CORNER.....



15" Balsam S 75 E 22.1'

10" Balsam S 20 E 16.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement for longitude and at the latitude prescribed by two DeLaMater property corners on the railroad and Old 27 ROWs. This seems to conform very nearly to DeLaMater's theoretical position for the 1/4 corner and also makes an equitable distribution of other affected lands.

Unable to locate any physical evidence of a previous corner in this area.



DISTRIBUTION:

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE  
10068

5-31-72

Forestry Division, Lansing