

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>●</u> , R. <u>4</u> W. <u>●</u>	<u>C-11; E-5; I-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 29, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- C-11 Found 1-1/2" pipe in block of concrete. Both OBT stps. in place; NE one with very good face.
- E-5 Found 1/2" iron bar as established in previous survey by James Richardson.
- I-12 Found 1-1/4" iron bar in road, used in other local surveys in this area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	E-5	I-12
DNR Monument	Set DNR Monument	1-1/4" Iron Bar
8" R. Oak N54°W 21.5'	6" R. Pine S06°W 71.1'	8" J. Pine S70°W 53.4'
6" R. Oak N54°E 15.2'	Twin Elm S60°E 102.6'	4" R. Pine N49°W 87.1'
OBT 14" W. Pine Stp. N21°E 37.7'	P.K. Nail in Face of P. Pine N53°E 40.8'	
OBT 18" W. Pine Stp. S64°W 40.2'		

SIGNED BY Kenneth J. Ostling DATE 8/23/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_