

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 28 N. R. 4 W.	K-1; K-3; L-3; M-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Crawford

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 14, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

C. (continued)

M-2
DNR monument & red top post
7" Ironwood S45°E 11.4
8" Beech S83°W 18.3
7" Ironwood N36°E 18.0


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-1 Found 1/2" rerod, 3 old white pine stump NBT's facing corner one with two hack marks and two with spikes in face of stump (no blaze).
- K-3 This corner was established at an average position of line over the 1/4 and section corners east, and the 1/4 and section corners south. No evidence of a previous corner.
- L-3 Found 1/2" rerod and two old NBT's (not of record) one with cabin spike and one with railroad spike in face.
- M-2 Found rotted stake point from DeLaMater southwest NBT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-1	K-3	L-3
DNR mon. & red top post	DNR monument	DNR mon. & red top post
24" W.P. stp. S11°E 47.3	6" Maple in clump of 3	11" Maple N22°E 60.6
20" W.P. stp. S66°E 42.1	N30°W 10.7	tw. 8" Ironwoods
2" R. Pine N37°W 38.9	8" Beech N40°E 24.9	S67°E 23.0
		4" Maple S18°W 21.5

SIGNED BY *Kenneth Ostling* DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)