

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 32 N.R. 4 W.


Charlevoix COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 11 - 14

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 16, 1962

WITNESSES TO CORNER.....



16" Elm S 73 W 0.8'

14" Elm N 73 E 10.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this area. Set corner by proportionate measurement, midpoint on line, between section corners. Unable to identify a 3" Elm NBT of record, although several large elm in vicinity. Could find no evidence of post when digging at possible location.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE

May 17, 1962