

SURVEY & REMONUMENTATION

MAR 08 1994

2 - 287

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

1993 DEC 10 PM 4: 25

For corners in

Table with columns: Charlevoix (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Charlene M. Roser
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Wayne E. Boss, in a field survey on September 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett
May 22, 1840. Set Post at
Intersections for corner T.
T32N & T33N - R4W & R5W.
1. Beech 18. N.28°E.37.
2. Beech 10. S.71°W.14.

Restored by E.A. Robinson
May 1906. Set Post Cor. to
T32N & T33N - R4W & R5W
from existing G.L.O. witnesses.

Marcus Schaaf set 1" x 24"
pipe that fits E.A. Robinson's
2' x 2' plts N-S-E-W.

December 8, 1981
Carl Roser, PS, replaced
Schaaf pipe with DNR Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Mon which was set by Carl Roser, PS, replacing 1" Schaaf pipe he found at Twp. Cor. Roser's cor. recital as recorded in Liber 2, Page 197, reads as follows:
A-1 - Fd. Schaaf Pipe Monument (1" x 24" pipe in sq. conc. block) that fits four E.A. Robinson 2' x 2' plts N-S-E-W. E.A.R. had U.S. B.T.s in his survey & Sec. Sub'n of Sec. 35 dated 1905.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Found DNR Mon. & Cedar Post per Liber 2, Page 197, Charlevoix County Records, Charlevoix County, Michigan, and is accepted as a careful and faithful perpetuation of the position of the original corner.
9" Maple S60°W 14.68' Fd. Blaze, Set Tag
8" Maple N48°W 21.32' Fd. Blaze, Set Tag
4" Twin Maple N50°E 8.45' Fd. Blaze, Set Tag
12" Maple S11°E 29.20' Set Blaze and Spike

Signed by [Signature] Date December 9, 1993

Surveyor's Michigan License No. 20703