

CHARLEVOIX COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO ACT 345, PA 1990

STATE OF MICHIGAN
 COUNTY OF CHARLEVOIX
 RECEIVED FOR RECORD
 1994 DEC 22 PM 1:57

Charlotte M. Probert
 REGISTER OF DEEDS

For corners in CHARLEVOIX (County)

	Located In:	Corner Code #
1. Public Land Survey	T 32N R 4W	A-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne E. Boss, in a field survey on September 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post corner Section 13 & 24 (T32N-R5W also cor. to Sec. 18 & 19 T32N-R4W)	Fd. post cor. Sec. 13 & 24 (T32N-R5W)	Fd. Post Cor. Sec. 13 & 24 (T32N-R5W)
1. Sugar 16" N14°E 13	1. Sugar 16" N14°E 13	Fd. Old Wit. E.A. Robinson 1902
2. Beech 8" S09°W 32	2. Beech 8" S09°W 32	
John Mullett May 1840	Wm. Burt July 6, 1850	

Fd. Post cor. Sec. 13 & 24 T32N-R5W	Fd. 1" pipe with wit. origin unknown
Old { 1. Sugar 16" N14°E 13 Rotten-down	1. Fd. Blz. set tag 36" Maple S06°E 14.00'
2. Beech 8" S09°W 26 Alive	2. Fd. Spk. 6" Maple N89°W 31.92'
EKR 3. Beech 18" S72½°W 46 Stump	3. Fd. Spk. 14" Maple N28°W, 20.27'
EKR 4. Beech 8" S09°W 26	4. Underground cabl. marker N42°E 48.05'
1929 EAR 5. Hemlock 11" N75½°W 61	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1" pipe fd. Origin Unknown	GLO to A-6 2640 meas. 2644.62'
Also found wit.	GLO to A-8 2640 meas. 2647.49'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Charlevoix County mon. set
 1. Fd. Blz - set tag 36" Maple S06°E 14.00'
 2. Fd. Spk. 6" Maple N89°W 31.92'
 3. Fd. Spk. 14" Maple N28°W 20.27'
 4. Underground cable marker N42°E 48.05'

And is accepted as the best available evidence of the position of the original corner.

Charlevoix Co. Surveyor
APPROVED
 Signature Wayne E. Boss
 Date Dec 16, 1994

PR 345, PA 1990

Signed by Wayne E. Boss
 Wayne E. Boss, PS
 Surveyor's Michigan License No. 20703

Date December 14, 1994

