

REMONUMENTATION
APR 08 1995
COMMISSION

2-318

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD
1994 DEC 22 PM 2:01

CHARLEVOIX COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

Charlene M. Packer
REGISTER OF DEEDS

For corners in _____
CHARLEVOIX (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	32N	R	4W	A-10
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne E. Boss, in a field survey on September 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-----------------------------|---------------------------------|
| Set qr. Section post | Set T-Iron 4" cedar post |
| 1. Elm 40" N21°E 22 | Thomas Schweigert In 1960 |
| 2. Beech 20" S19°W 39 | 1. 12" Beech S42°E 21.0 |
| John Mullett 1840 | 2. 15" S. Maple N10°E 2.2 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner set by Schweigert midway between NW & SW corners of Section 30 with corner registry in L1 page 50.
G.L.O. to A-9 2640 meas. 2647.54
G.L.O. to A-11 2640 meas. 2647.73

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10 Charlevoix Co. Mon. set replacing "T" Iron.
1. Fd. Spk. 14" Maple North 2.70'
 2. Fd. Spk. 13" Maple N70°E 16.05'
 3. Fd. Spk. 16" Beech S43°E 21.76'
 4. Fd. Spk. 12" Maple S75°W 20.72'
- And is accepted as a careful and faithful reestablishment of the position of the original corner.

Charlevoix Co. Surveyor
APPROVED
Signature Wayne E. Boss
Date: Dec 14, 1994

Signed by Wayne E. Boss Date December 14, 1994
Surveyor's Michigan License No. 20703

