

REMONUMENTATION
 APR 06 1995
 COMMISSION

CHARLEVOIX COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CHARLEVOIX
 RECEIVED FOR RECORD

1994 DEC 22 PM 2:02

Charlene M. Peckin
 REGISTER OF DEEDS

For corner in _____
 Located In: _____ Corner Code ##

1. Public Land Survey	T	<u>32N</u>	R	<u>4W</u>	<u>A-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne E. Boss, in a field survey on September 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post corner Sections 25 & 2
 T32N-R5W (Also cor. to Sec. 31 & 30,
 T32N-R4W.)
 1. Beech 8" N33°E 34
 2. Beech 6" S52°W 30
 John Mullett 1840

Fd. Post Sec 25 & 26
 Wit. good. E. K.
 Rodinson March 1878
 1. Beech 8" N33°E 24
 Fd. again 1902. EKR

Conc. Mon. set w/4" cedar post
 1. 5" H. Maple S59°E 10.6
 2. 16" H. Maple N16½°E 29.3
 Thomas Schweigert June 1958

Fd. Conc. Mon. w/sq. cedar post.
 Re-wit
 1. 5" Maple N09°W 22.3'
 2. 6" Maple N51°E 20.6'
 3. 7" Maple S47°E 22.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Conc. Mon. set by proportional measurement, as recorded in corner Registry L1 page 13 & L1 page 62.
 Carl Roser also fd. conc. mon. in 1972 and recorded corner certification L1 page 46.
 G.L.O. to A-10 2640 meas. 2647.73'
 G.L.O. to A-12 2640 meas. 2616.05'
 A-12 to A-13 meas. 2615.83'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Fd. Conc. Mon. & squared cedar post,
 1. Fd. Tag # 6525 10" Basswood West 8.80'
 2. Fd. Spk. 6" Maple N06°W 22.62'
 3. Fd. Spk. 10" Maple S45°E 21.34'
 4. Fd. Spk. 8" Maple N45°E 22.93'
 And is accepted as a careful and faithful reestablishment of the position of the original corner of

Charlevoix Co. Surveyor
APPROVED
 Signature Wayne E. Boss
 Date: Dec. 14, 1994



Signed by Wayne E. Boss, PS
 Surveyor's Michigan License No. 20703

Date December 14, 1994

LIBER **002** PAGE **319**