

2-320

CHARLEVOIX COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD  
 1994 DEC 22 PM 2: 03

For corners in  
CHARLEVOIX  
 (County)

ALSO ACT 345, PA 1990

*Charlene M. Pascher*  
 REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>4W</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne E. Boss, in a field survey on September 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set qr. Section post	Fd. qr. Section post	Set DNR Mon.
1. Sugar 8" N58°E 22	Re-wit	1. 24" Beech S23°W 72.7'
2. Sugar 8" S55°W 26	1. Hemlock 12" N64¾°E 33	2. 14" Maple N48°W 53.3'
John Mullett 1840	2. Sugar 22" S53°W 31	3. 8" Apple 4-clstr. S50°E 73.3'
	E. K. Robinson March 1878	4. E-W Trail Road Due North 115'
	Fd. again EKR 1902	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set DNR Mon. reestablished per standard BLM instructions by Carl Roser 1972, and as recorded L1 page 46.

G.L.O. to A-11 2640 meas. 2616.05'  
 G.L.O. to A-13 2640 meas. 2615.81'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-12 Found DNR Mon. 120' South of 2-track.
1. Fd. Blz. in 24" Beech S23°W 73.00'
  2. Set Nail & Tag 4" Ironwood East 3.98'
  3. Set Nail & Tag 6" Cherry North 16.65'
  4. Set Nail & Tag 4" Ironwood N85°W 14.27'
  5. Set Nail & Tag 4" Maple S22°W 28.87'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *Wayne E. Boss*  
 Surveyor's Michigan License No. 20703

Date December 14, 1994

Charlevoix Co. Surveyor  
**APPROVED**  
 Signature *May C. Fenwick*  
 Date: *Dec 14, 1994*

