

**SURVEY & REMONUMENTATION**

MAR 08 1994

*E-288*

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD

1993 DEC 10 PM 4:26

*Charlene M. Bishop*  
 REGISTER OF DEEDS

For corners in

Charlevoix (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 4W	B-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on September 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett May 1840  
 Set 1/4 Sec post  
 1. Sugar 14. N.71°E.30.  
 2. Beech 8. N.63°W.36.

Restored 1/4 cor. per E.A. Robinson May 14, 1906.  
 Set 1/4 Sec Post from G.L.O. witnesses. Still in and OK.

Marcus Schaaf set 2" pipe for 1/4 cor. (Carl Roser determined Schaaf cor. to be erroneous and 34.9' South of actual cor.)

Restored 1/4 Cor. 2/7/86 by Carl Roser PS. DNR Mon. set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Found DNR Mon, which was corner restored by Carl Roser, PS, and whose method of restoration is recorded in Liber 2, Page 201, and reads as follows:**

B-1 - Restored S 1/4 corner Sec. 31 (T33N-R4W), N 1/4 corner Sec. 6 (T2N-R4W), per E.A. Robinson survey of N. line of Sec. 6, dated May 14, 1906; see Hudson (32-4), Bk. C-296, pg. 10, at Jury Room in courthouse. Robinson's notes say "at 21.25 ch. W. of 1/4 Corner - small spring, rivulet that soaks into ground on his random between fd. 1/4 Corner from Govt. B.T.'s" (spring was on line extended W. bet. NE & N 1/4 Cor. of Sec. 6 (32-4). We recovered this spring, very definite, to restore 1/4 Cor. & pro-rated to E. A. Robinson bet. fd. NE & NW of Sec. 6. Fits his var. of the compass reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Found DNR Mon. & Cedar Post per Liber 2, Page 201, Charlevoix County Records, Charlevoix County, Michigan, and is accepted as a careful and faithful reestablishment of the position of the original corner.

5" Maple	N20°E	15.1'	Fd. Blaze & Tags
6" Maple	S88°E	35.5'	Fd. Blaze & Tags
6" Ironwood	S48°E	25.1'	Fd. Blaze & Tags
4" Maple	N60°W	38.5'	Fd. Blaze & Tags
2" Schaaf pipe (drove flush)	N67°11'E	89.3'	

Signed by *Wayne E. Boss* Date December 9, 1993

Surveyor's Michigan License No. 20703