

MAR 0 8 1994 COMMISSION

For corners in

expressed below:

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

jî.	- temporal and a second second
	STATE OF MICHIGAN COUNTY ARLEVOIX RECEIVED LUR RECORD

	Comers in			HEACLLED LAK KECOSO
	Charlevoix	Located In:	Corner Code ##	· · · · · · · · · · · · · · · · · · ·
	(County)			1993 DEC 10 PH 4: 27
1.	Public Land Survey	T <u>32N</u> R <u>4W</u> T R T R T R	C-1	REGISTER OF DEEDS
2.	Property Controlling in Section	S T R S T R		•
3.	Miscellaneous	S R		Contain of Book Ob A William A
	Property in Sec.	S T R		Register of Deeds Stamp & File Number
4.	Lot No	, Recorded Plat		
5.	Private Claims			A B C D E F G H I J K L
				2 - 6 - 5 - 4 - 3 - 2 - 1
				3
				4 7 4 9 10 10 11
Í,	Wayne E. Boss	, in a field survey on <u>Septe</u>	ember 23 19 93	
do	hereby certify that under r	requirements of P.A. 74, Michigan P.A.	of 1970, the corner points mention	oned a
in i	ines 1 and 2 above were	in conformance with regulations and	d rules therefore as required in	the 5 18 17 16 15 14 13
CUI	rent manual of survey ins	structions of the United States Depart	ment of the Interior, Bureau of L	and 'l <del></del>

on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded

Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as

G.L.O. John Mullett May 1840 Set Post comer Sections 31 & 32 (T33N-R4W) (also Sec. 5 & 6, T32N-R4W) 1. Beech 10. N.77°E.34.

2. Beech 8. N.38°W.28.

11

Restored by E.A. Robinson May 1906. Set post Cor. Sections 31 & 32 (from original 1840 G.L.O. witnesses, verified & reused)

Marcus Schaaf set 2" pipe for Cor common to Sections 31 & 32, T33N-R4W, and Sections 5 & 6, T32N-R4W, which Carl Roser determined to fit stream tie & E.A. Robinson tie.

10

12

December 19, 1985 Carl Roser, PS, replaced 2" Schaaf pipe with DNR Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Mon set by Carl Roser replacing 2" Schaaf pipe he found at Sec. Cor. Roser's corner recital as recorded in Liber 2, Page 198, reads as follows:

- C-1 Fd. Marcus Schaaf 2" plpe mon. for Sec. cor. comm. to Sec's 31 & 32 (T33N-R4W) & Sec's 5 & 6 (T32N-R4W). Fits U.S. stream tie 1198'± N., 279'S. & E.A. Robinson tie's west 1-mile (to very definite spring that soaks into ground & twp. cor.) along N. line of Sec. 6 (T32N-R4W); see Hudson (32-4), Bk. C-296, Pg. 10, dated May 14, 1906; notes in jury room in courthouse.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1	Found DNR Mon. & ( Michigan, and is acce) 6" Maple 3" Maple 7" Maple 9" Maple	Cedar Post pe pled as a caref N26°W N68°E S62°E S45°W	8.6' 13.5' 22.0'	e 198, Charlevoix County Records, Charlevoix County, perpetuation of the position of the original corner. Fd. Blaze & Tag Fd. Blaze & Tag Fd. Blaze & Tag
		<b>-</b>	26.9' 107'	Fd. Blaze & Tag Fd. Blaze & Tag

Signed by Way	MESon	DateDecember 9, 1993	_
Surveyor's Michigan License No.	20703		