

**SURVEY &
REMONUMENTATION**

MAR 21 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

96 OCT 29 AM 11:44

For corners **COMMISSION**
Charlevoix

Charles M. Cobles
REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR 4W</u>	<u>E-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James E. Evans, in a field survey on Nov. 20, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3					●								
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-3 CORNER COMMON TO SEC 4, 5, 8 and 9 T32N-R4W

GLO: Set Hemlock post 14" Sugar N16°W 31 lks (20.46') 14" Sugar S53°E 6 lks (3.96') by William Burt, DS, 1840	Circa 1904 E. A. Robinson Chx. Co. Surveyor Bk 6 Pg 38 Corner is RR steel 45# & 36" long 8" Sugar S88 1/2°W 63 lks (41.58') 8" Hemlock N49°E 80 lks (52.80') Also stones around post RR siding is 21 lks (13.86') East
--	--

1963 Mary C. Feindt found RR rail disturbed.
Placed spike South of rail on fence to West.
Field notes in job #S-359.
No new witnesses.

1967 Mary C. Feindt recorded "Plat of Thunder Village" Liber 2 Pages 125-126.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 4" concrete monument as shown on "Plat of Thunder Village".

GLO to E-4 = 2640
E. K. Robinson = 2636.04
Art Ranger, PS #31601 = 2640.84

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: Oct. 10, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Witnesses to concrete monument as shown on "Plat of Thunder Village"

Power pole S25°E 40.70' found Pk nail
Concrete monument N85°W 36.17' (Rec 36.19')
28" Maple S65°W 47.27' found nail in East side
11" Maple N60°E 63.27' set nail & cap #16034
Center asphalt road N86°E ± 13.2'

And is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by James E. Evans
Surveyor's Michigan License No. 22431

Date 10-10-96