

**SURVEY & REMONUMENTATION**  
**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD

1993 DEC 10 PM 4: 30

*Charlotte M. Robinson*  
 REGISTER OF DEEDS

For corners in

<u>Charlevoix</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>4W</u>	<u>F-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne E. Boss, in a field survey on September 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**G.L.O. John Mullett**  
**May 1840. Set 1/4 Sec. Post.**  
 1. Beech 8. N.46°W.10.  
 2. Beech 6. N.43°E.32.

**Restored by E.A. Robinson**  
**In May 1906. Set 1/4 Sec.**  
**Post from existing G.L.O.**  
**witnesses.**

**Marcus Schaaf set 2" pipe**  
**at location Carl Roser, PS,**  
**determined to be erroneous.**

**December 20, 1985**  
**Carl Roser, PS, set DNR Mon. at**  
**E.A. Robinson location.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Fd. DNR Mon. set by Carl Roser, PS, and whose method of restoration is recorded in Liber 2, Page 197, and reads as follows:**

**F-1 - Fd. N 1/4 Cor. of Sec. 4, T32N-R4W (S 1/4 Cor. Sec. 33, T33N-R4W) per E.A. Robinson survey of North line of Sec. 4 dated May 1906; see Hudson (32-4) Book C-296, Pg.3. Restored cor. from E.A. Robinson N.B.T. (Hemlock Stp remains, S64°E, 22.4'). Fits E.A. Robinson tie 10.00 chains East to stream 20 Lks. wide. Any other latitude for 1/4 Cor. would not fit stream tie. Also fits E.A. Robinson distance 1/2 mile east (very close) to fd. SE Sec. 33. E.A. Robinson fd. both U.S. B.T.s at S 1/4 cor. of Sec. 4. Fd. Schaaf 2" pipe (dug pipe down flush w/ground), N61°18'E, 98.2'.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**F-1 Found DNR Mon. & Cedar Post per Liber 2, Page 197, Charlevoix County Records, Charlevoix County, Michigan, and is accepted as a careful and faithful reestablishment of the position of the original corner.**

6" Maple	N45°E	31.8'	Fd. Blaze & Tag
10" Maple	S70°E	31.0'	Fd. Blaze & Tag
12" Maple	S35°W	30.3'	Fd. Blaze & Tag
14" Twin Maple	N40°W	9.0'	Fd. Blaze & Tag

Signed by Wayne E. Boss Date December 9, 1993  
 Surveyor's Michigan License No. 20703