

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD

97 JAN -9 PM 3: 32

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHARLEVOIX  
 (County)

Located in:

Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>32NR 4W</u>                          | <u>1-2</u>  |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

*Mary C. Feindt*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, ARTHUR R. RANGER, in a field survey on SEPT. 11, 19 93 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3	●	2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1850- GLO-SET QR. SEC. POST - WITNESSES: SUGAR 10" N85°E 25LKS; SUGAR 14" S24°W 23LKS.
  - 1906- E.A. ROBINSON, SURVEYOR RESET THE CORNER IN A SURVEY, AND WITNESSED: SUGAR 10" N85°E 25LKS; SUGAR 14" S24°W 23LKS; HEMLOCK 36" S78.75°E 71.5LKS; SUGAR 18" N89°W 28LKS.
  - 1920- GLO IN A SURVEY DATED 04/26/21 RESET THE QR. SEC. CORNER. WITH A BRONZE DISC.
  - 1974- BIDSTRUP & YOUNG USED THE GLO CORNER IN A SURVEY OF THE MEADOWS SUBDIVISION.
  - 1982- CARL ROSER, SURVEYOR (DNR) USED THE CORNER IN HIS RETRACEMENT SURVEY.
  - 1986- LARRY FEINDT, SURVEYOR USED THE CORNER IN HIS SURVEY OF THE ASSESSOR'S PLAT OF HORNER ISLAND.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1993- ARTHUR R. RANGER, SURVEYOR FOUND THE BRONZE DISC WITH PIPE AS SET BY THE GLO IN THEIR SURVEY ABOVE MENTIONED. (REFER TO THE 1920 GLO SURVEY).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2 FOUND GLO BRONZE DISC WITH PIPE  
 14" OAK NORTH 35.05'  
 10" MAPLE S70°E 10.82'  
 10" MAPLE N80°W 18.62'  
 8" MAPLE SOUTH 3.05'

**SURVEY & REMONUMENTATION**

NOV 21 1997

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

COMMISSION

Signed by Arthur R. Ranger Date 11/13/96  
 Surveyor's Michigan License No. 31601

Charlevoix Co. Surveyor

**APPROVED**

Signature Mary C. Feindt

Date: Jan 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

