

**SURVEY & REMONUMENTATION**

MAR 08 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD

1993 DEC 15 PM 4:37

For corners in

<u>CHARLEVOIX</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>4W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Charlene M. Paschen*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, ARTHUR R. RANGER, in a field survey on SEPT. 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1 GLO-- SET QR. POST - BEECH 14" N42°W 20 LKS; SUGAR 12" N28°E 19 LKS;  
 E.K. ROBINSON RESET QR. SECTION POST IN A SURVEY DATED 1881- WITNESS: BEECH 14" N42°W 20 LKS; SUGAR 12" N28°E 19 LKS;  
 WAYNE BOSS P.S. 20703 RESET THE CORNER WITH A 1/2" IRON ROD IN A SURVEY DATED NOV. 28, 1973- WITNESS: SPIKE IN TREE S36°E 16.90'; SPIKE IN TREE S5°E 43.82'; SPIKE IN TREE N60°W 41.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 FOUND 1/2" ROD AND WITNESSES; BOSS CORNER FALLS 8.70' SOUTH & 14.23' EAST OF THE TRUE POSITION OF CORNER BASED ON ESTABLISHING ITS POSITION HALFWAY AND ON LINE BETWEEN SECTION CORNERS TO THE EAST AND WEST.  
 SET HARRISON MONUMENT HALFWAY AND ON LINE BETWEEN SECTION CORNERS AT THE CORNERS TRUE POSITION. (SEE L.C.R.C. FOR I-1 BY ART RANGER; THE CORNERS POSITION SHIFTED BECAUSE OF THE CORRECTED POSITION OF I-1).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 SET HARRISON MONUMENT  
 WITNESS:  
 12" MAPLE S50°W 25.34'  
 14" MAPLE S6°E 20.61'  
 18" MAPLE S44°E 32.72'  
 12" ASH S79°E 20.40'  
 1/2" ROD S50°E 16.68'



Signed by Arthur R. Ranger  
 Surveyor's Michigan License No. 31601

Date 12/13/93