

SURVEY & REMONUMENTATION

MAR 08 1994

COMMISSION

2-293

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED RECORD

1993 DEC 15 PM 4: 34

Charlene M. Boehlert
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 4W
T 32N R 4W
K-1
L-1
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Markers K-1 and L-1 are indicated at the intersection of columns K and L, rows 1 and 2.

ARTHUR R. RANGER, in a field survey on SEPT. 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 GLO - SET POST- BEECH 10" N52°E 13 LKS; SUGAR 16" N29°W 14 LKS; E.K. ROBINSON COUNTY SURVEYOR SET POST IN A SURVEY DATED 1881- WITNESS: SUGAR 24" S34°W 34.5 LKS; BEECH 10" N52°E 13 LKS; SUGAR 16" N29°W 14 LKS; ELM 2" N43-1/2°E 39 LKS
L-1 - GLO - SET POST - BEECH 14" N64°E 30 LKS; BEECH 10" N80°W 18 LKS; E.K. ROBINSON COUNTY SURVEYOR RESET QUARTER CORNER IN A SURVEY IN 1881- WITNESS- SUGAR 4" N38°E 16 LKS; SUGAR 10" N80°W 18 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 FOUND LARGE 2" IRON PIPE 4" BELOW GRADE IN A ROAD INTERSECTION; ORIGIN OF CORNER UNKNOWN; FITS OCCUPATION N., S., E. & W., AND IS BEING USED BY OTHERS IN SURVEYS; HELD 2" IRON PIPE; RAISED CORNER UP WITH A HARRISON MONUMENT.
L-1 FOUND 1/2" ROD USED BY OTHERS IN SURVEYS ACCORDING TO GEORGE J. AVENDT JR., P.S. 16034. (NOTE: FOUND 1/2" ROD IS 0.31' NORTH & 2.45' WEST OF A TRUE SPLIT AND ON LINE). HELD 1/2" IRON ROD- ORIGIN UNKNOWN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 SET HARRISON MONUMENT OVER 2" IRON PIPE WITNESS: 9" MAP. N44°W 21.03' 9" IRONWOOD S84°W 52.91' 4" IRONWOOD S50°W 21.31' 1/2" ROD SOUTH 33.27' 20" MAP. S8°E 14.37'
L-1 REPLACED 1/2" ROD W/HARRISON MONUMENT WITNESS: 10" MAP. N24°W 5.65' 5" MAP. N44°E 7.00' 6" BEECH N82°E 13.71' 9" MAP. S12°W 6.59'



signed by Arthur R. Ranger

Date 12/02/93

Surveyor's Michigan License No. 31601