

**SURVEY & REMONUMENTATION**

MAR 08 1994

COMMISSION

2-296

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

1993 DEC 15 PM 4:36

*Charlene M. Cookin*  
REGISTER OF DEEDS

For corners in

CHARLEVOIX  
(County)

Located In:

Corner Code #

- |                                    |   |            |   |           |            |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>32N</u> | R | <u>4W</u> | <u>M-1</u> |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section | S | _____      | T | _____     | _____      |
|                                    | S | _____      | T | _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____     | _____      |
|                                    | S | _____      | T | _____     | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ARTHUR R. RANGER, in a field survey on SEPT. 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-1 GLO- SET POST ON BANK OF POND- PINE 16" N2°W 38 LKS; PINE 16" S51°E 50 LKS; E.K. ROBINSON COUNTY SURVEYOR FOUND CORNER IN A SURVEY DATED 1881- WITNESS- PINE 16" N2°W 38 LKS; PINE 16" S51°E 50 LKS; PREVIOUSLY RECORDED BY CARL I. ROBINSON, OTSEGO COUNTY SURVEYOR IN A SURVEY DATED 1987; (CO. SURVEY REC. L.4, P.482) PINE 16" S51°E 50 LKS; PINE 16" N2°W 38 LKS; FOUND A 1" IRON PIPE & CONCRETE MONUMENT & PINE STUMP REFERENCE, USED CONCRETE MONUMENT BECAUSE IT FIT PINE STUMP REFERENCE.

\*SEE REVERSE SIDE FOR REMARKS BY CARL I. ROBINSON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 FOUND CONCRETE MONUMENT AND 1" IRON PIPE AND ROBINSON WITNESSES PREVIOUSLY RECORDED; HELD CONCRETE MONUMENT. (FOUND OLD PINE STUMP WITNESS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 FOUND CONCRETE MONUMENT & IRON PIPE  
WITNESS:

- 20" W. PINE N40°W 6.33'
- OLD PINE STUMP N6°E 25.4'
- 8" POPLAR N41°E 12.61'
- 10" W. CHERRY S28°E 24.37'
- ED. OF LAKE WEST 11.50'
- 9" MAPLE S80°E 8.14'



Signed by Arthur R. Ranger

Date 12/02/93

Surveyor's Michigan License No. 31601

M-1 (CO. SURVEY REC. L.4, P482) PINE 16" S51°E 50LKS; PINE 16" N2°W 38 LKS.

M-1 FOUND 1" I. PIPE, CONCRETE MONUMENT AND PINE STUMP REFERENCE. USED CONC. MON. BECAUSE IT FIT PINE STUMP REFERENCE.

M-1 CONCRETE MONUMENT: 6" ASPEN N35°E 12.85'; 16" W. PINE N72°E 31.95';  
8" TWIN CHERRY S25°E 24.78'; 16" W. PINE N35°W 6.89'

*Handwritten notes on the left margin:*  
H. K. Ranger  
S. 1/4 Sec. 36  
T. 12 N. R. 10 W.  
S. 1/4 Sec. 36  
T. 12 N. R. 10 W.

*Handwritten notes on the right margin:*  
12/8/81  
12/8/81