

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 32 N., R. 5 W.	C-11; C-12
2. PROPERTY CONTROLLING IN SECTION 32	T. 32 N., R. 5 W.	10
3. MISCELLANEOUS PROPERTY IN SECTION 32	T. 32 N., R. 5 W.	XX (663.4' S of D-12 & 1,990.3' N of D-13)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 5, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on August 5, 1975, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~

C. (continued)

XX  
Set 1 1/2"x36" pipe & cedar post w/loc. tag  
7" Cedar S32°E 10.2  
7" Cedar S42°W 22.1  
9" Cedar N84°W 30.0  
8" Cedar N01°W 43.9

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Restored corner at double distance & on line across section corner & 1/4 corner to N. This corner fits US tie west to stream (now old streambed which is still very evident - present stream in newer position); corner falls in marshy pasture; if above corner had been placed to S it would not fit distance W to stream & stream direction would have been incorrect.
- C-12 Reestablished corner per standard B.L.M. instructions.
- 10 Established corner equidistant and on line between SW and W 1/4 of Section 32.
- XX Established SE corner of N 1/2-N 1/2-SW 1/4 of Sec. 32 at 663.4' south of center of Sec. 32, on N-S one-quarter line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	C-12	10
Drove 1 1/2"x48" pipe in pasture, surrounded by stones & set cedar post	DNR mon. & cedar post	Set 1 1/2"x36" pipe & cedar post w/loc. tag
4" Spruce N60°E 42.0	12" Maple S58°W 28.1	6" Twin Maple N79°W 12.4
35" W.Pine Stub PK in side (12'high) N17°W 239.69	7" Maple N78°W 18.0	9" Tri-Maple S39°W 29.2
PK in side of Hi-Line Power Pole S80°W 194.32	14" Tri-Maple S28°E 7.3	5" Ironwood N64°E 40.6
Old N-S fence Due E 22'	Old N-S b'wire fence Due E 8.5	N-S Random Due W 10.9
Random Line E Due S 8'	N-S random Due W 21.8	Old N-S Fence Due W 25.3
		Old E-W Fence Due S 28.5

SIGNED BY Carl F. Roser 4-26-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BOYNE VALLEY TOWNSHIP  
CHARLEVOIX COUNTY