

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>32</u> ^{N.} _{6.} , R. <u>5</u> ^{W.} _{4.}	<u>H-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	T. <u>32</u> ^{N.} _{6.} , R. <u>5</u> ^{W.} _{4.}	<u>16, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 15, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-3 Fd. & accepted 1" pipe for south 1/4 corner of Sec. 3. Corner falls at position of old corner fence post (down), fence remains south and west. Corner fits E.A. Robinson survey of South line of Sec. 3, dated 1913.
- 16 Fd. 1 1/4 " pipe for SE corner of SW 1/4-SE 1/4 of Sec. 3; fits E.A. Robinson's 1913 survey of the South line of Sec. 3. Corner falls by old corner fence post; fence remains N-S-E.
- 14 Estab. S1/8 cor. on East line of Sec. 3 midway and on line between E1/4 corner and SE corner of Sec. 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3	16	14
Fd. 1" pipe added ced. post.	Fd. 1 1/4" pipe added ced. post	Set 5/8" x 36" rerod w/RLS cap.
14" Tamarack N25°E 26.1	8" Cedar S85°W 29.3	6" Cedar S70°E 61.8
5" Tamarack S45°E 33.2	12" Cedar S55°E 22.1	7" W. Birch (twin) S45°W 62.5
10" Tamarack S85°W 12.9	6" Cedar N65°E 29.2	6" Cherry N80°W 57.6
Stream C-S SW West 353' Mea. & Rec.-U.S.		Set ced. post w/loc tag West 33'
		Old E-W grade North 75'±
		Old fence to East South 10'±


SIGNED BY Carl F. Roser 01-12-82 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHARLEVOIX COUNTY
BOYNE VALLEY TOWNSHIP

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET