

SURVEY & REMONUMENTATION COMMISSION
 APR 06 1995

2-341

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

BOYNE VALLEY TOWNSHIP

For corners in
CHARLEVOIX
 (County)

Located In:	Corner Code #
T 32N R 5W	A-2
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

STATE OF MICHIGAN
 COUNTY OF CHARLEVOIX
 RECEIVED FOR RECORD

1994 DEC 22 PM 2:16

Charlene M. Beckin
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling In Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

George J. Avendt, JR. NOV. 21 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2 QUARTER CORNER COMMON TO SEC. 6, T32N, R5W. & SEC. 1, T32N, R6W.
 SURVEYED IN 1839 BY JOHN HODGSON, DS - G.L.O. - SECTION 1/4 POST BEECH 12" N18°W 13 LINKS (8.58') - SUGAR 12" N32°W 15 LINKS (9.9')
 SURVEYED 1974 BY CARL F. ROSER, PS 12028. FOUND CHARLEVOIX COUNTY MONUMENT FOR W 1/4 CORNER, SEC. 6
 16" MAPLE N88°E 43.0' - 26" MAPLE N05°E 6.00' IN FENCE CORNER OLD FENCE N-S-E-W LIBER 2, PAGE 5

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 QUARTER CORNER COMMON TO SEC. 6, T32N, R5W. & SEC. 1, T32N, R6W.
 FOUND CHARLEVOIX COUNTY ALUMINUM CAP ON 1" PIPE
 24" MAPLE N00°W 6.05 (NOT FOUND)
 CEDAR POST S00°E 0.60 CHECKS ROUGH
 12" MAPLE N90°E 43.00 (MEAS. 43.10')

Charlevoix Co. Surveyor
APPROVED
 Signature *Mon C. Fawcett*
 Date: *Dec. 8, 1994*
 P.A. 345 of 1970

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 QUARTER CORNER COMMON TO SEC. 6, T32N, R5W. & SEC. 1, T32N, R6W.
 FOUND CHARLEVOIX COUNTY ALUMINUM CAP ON 1" PIPE
 S88°E 43.10' 17" MAPLE/CAP # 10710
 N12°W 25.90' 7" IRONWOOD/MSHD TAG
 N08°E 6.47' 29" MAPLE/MSHD TAG
 N83°W 13.37' 4" IRONWOOD/CHARLEVOIX COUNTY TAG
 N25°E 30.09' 10" IRONWOOD/MSHD TAG



Signed by *George J. Avendt, Jr.* Date *4 Dec. 1994*
 Surveyor's Michigan License No. 16034

LIBER 002 PAGE 341

FILE

9.00 2.00

CONTINUED

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

LAND CORNER RECORDATION CERTIFICATE
BY LAWRENCE R. FEINDT, PS 21566 DATED JAN-30-1975
FOUND DNR DISK ON NORTH AND SOUTH FENCE AT INT. WITH FENCE RUNNING EAST.
24" MAPLE N00°W 6.05'
CEDAR POST S00°E 43.0'
12" MAPLE N90°E 43.0'
LIBER 2, PAGE 4