

SURVEY & REMONUMENTATION
APR 06 1995
COMMISSION
 For corners in CHARLEVOIX (County)

2-349

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Boyne Valley Township

| | | |
|---------------------------------------|-------------------------|---------------|
| | Located In: | Corner Code # |
| | 32N 5W | A-9 |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
 COUNTY OF CHARLEVOIX
 RECEIVED FOR RECORD

1994 DEC 22 PM 2:22

Charlene M. Cook
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

George J. Avenedt, JR. NOV. 16 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

A-9 CORNER COMMON TO SEC'S. 19 & 30, T32, R5W. & SEC'S. 25 & 36, T32N, R6W. SURVEYED IN 1839 BY JOHN HODGSON, DS - G.L.O. - SET SECTION POST TAMARACK 10' S60°W 20 LINKS (13.2') - TAMARACK 24" N40°W 25 LINKS (16.5') SURVEYED 1975 BY CARL F. ROSER, PS 12028. FOUND CHARLEVOIX COUNTY MONUMENT W/CAP BROKEN; ADDED 3/4"X12" BOLT W/NUT IN PIPE; CORNER IS IN CENTER OF N-S BLACKTOP COUNTY ROAD; RANDOM LINE TO EAST IS SOUTH 5.1'. 12" TAMARACK N47°E 113.3' - 10" CEDAR S61°E 84.3' - 9" CEDAR S68°W 63.0' - 7" CEDAR N63°W 72.0' - SET CEDAR POST DUE E 33' (LIBER 2, PAGE 46)
 CONTINUED ON BACK


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 CORNER COMMON TO SEC'S. 19 & 30, T32, R5W. & SEC'S. 25 & 36, T32N, R6W. FOUND 3/4"X12" BOLT IN 1-1/4" PIPE OVER CHARLEVOIX COUNTY MARKER

Charlevoix Co. Surveyor
APPROVED
 Signature *George J. Avenedt, Jr.*
 Date: *Dec. E. 1994*
 P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 CORNER COMMON TO SEC'S. 19 & 30, T32, R5W. & SEC'S. 25 & 36, T32N, R6W. FOUND 3/4"X12" BOLT IN 1-1/4" PIPE OVER CHARLEVOIX COUNTY MARKER
 N89°W 33.24 1/2" IRON ROD/CAP # 24595
 N60°W 48.32' 4" POPLAR/CAP # 16034
 N36°W 70.75' 6" CEDAR/CAP # 16034
 S88°E 33.7' 6" DNR CEDAR POST
 S59°E 84.31' 13" CEDAR/ CAP # 16034



Signed by *George J. Avenedt, Jr.*
 16034

Date *8 Dec 1994*

Surveyor's Michigan License No. _____

LIBER 002 PAGE 349

FILE

1000
200

CONTINUED

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

CERTIFICATE OF SECTION, QUARTER, MEANDER CORNER REGISTRY
BY BEN SEIFERT, PS 7273 DATED 11-13-1964 LIBER 1, PAGE 53
SET C.C.M. FROM CONSTRUCTION WITNESSES 0.05'± BELOW SURFACE (ORIGINAL 3" PIPE
WAS LOST DURING CONSTRUCTION)

6" SPRUCE 55° 95.5'
8" SPRUCE 223° 95.8'
8" TW. SPRUCE 290° 59.0'