

SEP 12 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

95 AUG -4 AM 9: 17

Charlene M. Coakley
REGISTER OF DEEDS

For corners in

<u>Charlevoix</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>5W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on May 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Set Post Cor Secs 31 & 32 (T33N-R5W which is also cor. to Sec 5 & 6 T32N-R5W)	Ironwood corner post E.A. Robinson, May 1906 Set 1"x40" Iron Stake, Dec 1913, no mention of witnesses.
1. Sugar 16N 35E 68	
2. Sugar 14N 83W 32	
John Mullett, May 1840	

Fd 1"x40" Robinson pipe and set
DNR Mon and Cedar Post in 1974
Carl Roser LCRC L. 2 Pg 6
3. 8" Maple S23°E 6.66
4. 10" Maple N11°E 21.65
5. 9" maple N84°W 13.40
6. In fence cor fence N-S-E-W
Used in subsequent surveys -
same unit

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DNR Mon Fd

3. Fd Spk 10" Maple S23°E 6.78'
4. Fd Spk 12" Maple N11°E 21.72'
5. Fd Spk and Tag 10" Maple S23°E 6.78
6. Fd Spk 20" Poplar N45°W 10.35'

GLO to B-1 2640 Robinson 1913, 2630.4 Roser 1975 2634.3
GLO to D-1 2640 Roser 2623.63 1982

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Ferrett
Date July 20, 1995
PA 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 DNR Mon

3. Fd Spk 10" Maple S23°E 6.78'
4. Fd Spk 12" Maple N11°E 21.72'
5. Fd Spk and Tag 10" Maple S23°E 6.78
6. Fd Spk 20" Poplar N45°W 10.35'

And is accepted as a careful and faithful perpetuation of the position of the original corner.



Witnessed by *Wayne E. Boss* Date July 28, 1995
Surveyor's Michigan License No. 20703 LIBER 002 PAGE 385