

SURVEY & RE-MONUMENTATION

SEP 12 1995

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

95 AUG -4 AM 9:19

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. Baker
REGISTER OF DEEDS

For corners in

Charlevoix
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 5W E-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne E. Boss, in a field survey on May 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|--|----------------------------|--|--|---|---|
| GLO Set Post corner to Sec 32&33 (T33N-R5W also cor to Sec 4&5 T32N-R5W) | Fd NW cor Sec 4, 1881 EKR | Fd Cor Post 1. Fd Old Beech 14, N83W, 45 | Fd Cor Post 4. Lynwood 6, 5.2°E, 9 1/2 | T-Iron set at fence lines Mary Feindt, April 1974 | DNR Mon & Cedar Post Set Replacing T-Iron |
| 1. Beech 14, N83W, 45 | 45 | 3. Sugar 8, N83E, 23 | 1. Beech 16, N83W, 45 | 5. 15" Basewood S5°W, 6.40" | 5. 18" Basewood S15°W, 6.44' |
| 2. Beech 16, N84E, 39 | E.K. Robinson also in 1884 | 4. Lynwood 6, 5.2 1/2 E, 10 | E.A. Robinson, June 1909 | 6. 6" Maple S60°E, 17.70' | 6. 6" Maple S55°E, 17.73 |
| John Mullett 1840 | 3. Lynwood 15, S48E, 10 | E.A. Robinson, Dec 1905 | | 7. 8" Maple N'15°W, 7.60 | 7. 10" Maple N10°W, 7.4 |
| | 4. Lynwood 9, S50W, 12 | | | | 8. 6" Maple S75°W, 17.5' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DNR Mon Fd

- 5. Fd. 18" Basewood S15°W, 6.44'
- 6. Fd. 6" Maple S55°E, 17.73
- 7. Fd. 10" Maple N10°W, 7.4
- 8. Fd. 6" Maple S75°W, 17.5'

GLO to D-1 = 2640 Roser 2622.75
GLO to F-1 = 2640 Roser 2611.68

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feindt
Date: July 28, 1995
PA 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 DNR Mon Fd

- 5. Fd. 18" Basewood S15°W, 6.44'
- 6. Fd. 6" Maple S55°E, 17.73
- 7. Fd. 10" Maple N10°W, 7.4
- 8. Fd. 6" Maple S75°W, 17.5'



Signed by *Wayne E. Boss* And is accepted as a careful and faithful establishment of the position of the original corner. Date July 28, 1995

Surveyor's Michigan License No. 20703

LIBER 002 FOLIO 387