

SEP 12 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

95 AUG -4 AM 9:20

*Charles M. Barber*  
REGISTER OF DEEDS

For corners in

Charlevoix  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 32N R 5W F-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne E. Boss, in a field survey on May 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Set 1/4 Post

- 1. Hemlock 12 N 69 E 19
- 2. Hemlock 10 N 41 W 46
- Jchn Mullett 1840

Fd 1/4 Post

- 3. Twin Sugar 12, S87 1/2 W 17 lks
- 4. Twin Sugar 9, S83W, 3 1/2 lks
- E. A. Robinson, Sep 1906
- EAR also used it in May 1909

MDOT 1/2" fr. Bar doesn't say if Fd or Set

- 5. N11E, 7.50 16" Maple
- 6. S56°W, 17.03' 4" Twin Elm
- 7. S69°W, 7.19 4" Tri Maple, Feb 1946.

Roser in DNR Survey 1982

- Fd Conc Mon that he stated fit three M.S.H.D. witnesses
- Set Cedar Post w/loc. tag
- 5. 24" Maple N15°W, 6.62
- 7. 14" Triple Maple, S68°W, 7.57
- Possible #6 witness
- 6.a. 13" Maple Clump S32°E, 14.19
- LCRC L. 2 Pg 142

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Conc. Mon Fd (origin unknown)

- 5. Fd 24" Maple N15°W, 6.62
- 6.a. Fd 13" Maple Clump S32°E, 14.19 Possible #6 witness
- 7. Fd 14" Triple Maple, S68°W, 7.57

GLO to D-1 = 2640  
GLO to F-1 = 2640

Roser 2622.75  
Roser 2611.68

Charlevoix Co. Surveyor  
APPROVED  
Signature Mary C. Feindt  
Date: July 20, 1995  
P A 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Conc. Mon Fd

- 5. Fd 24" Maple N15°W, 6.62
- 6.a. Fd 13" Maple clump S32°E, 14.19 Possible #6 witness
- 7. Fd 14" Triple Maple, S68°W, 7.57
- 8. Set Spk in Cedar Post N45°W 1.11

And is accepted as a careful and faithful re-establishment of the position of the original corner.



Signed by *Wayne E. Boss* Date July 28, 1995  
Surveyor's Michigan License No. 20703