

SLP 1 2 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

95 AUG -4 AM 9:21

Charlene M. Barber
REGISTER OF DEEDS

For corners in COMMISSION

Table with columns: Charlevoix (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling In Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in cell G-3.

I, Wayne E. Boss, in a field survey on May 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
GLO Set Post Corner Stake & Gov't BTs Fd
Sec 33 & 34 (T33N-R5W, which is also cor to sec 3&4, T32N-R5W) Set Cedar 2 1/2"
1. Birch 10, N56W, 33
2. Hemlock 8 N77E, 27
3. Hemlock 12 S70E, 6
4. Hemlock 24, S13E, 20
John Mullett 1840
1. Birch 10, N56W, 24 instead of 33
2. Hemlock 8 row 14, N77E, 27.
3. Hemlock 12 row 16 S70E, 6
E.A. Robinson Sept. 1906

- Re-established corner
Set DNR-Mon and Cedar Post midway on line between F-1 and H-1 Roser, Jan 1981. Roser stated position fits E.A. Robinson Survey of 1906. LCRC L. 2 Pg 142
5. 9" B. Cherry N65°E, 12.9
6. 5" Maple S30°E, 42.8
7. 4" Maple S80°W, 31.9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DNR Mon Fd

- 5. Fd 9" B. Cherry N65°E, 12.9
6. Fd 5" Maple S30°E, 42.8
7. Fd 4" Maple S80°W, 31.9

GLO to F-1 2640 EAR 1906 - 2618.9 Roser 1981 2617.68
GLO to H-1 2640 Roser 1981 - 2617.68

Charlevoix Co. Surveyor
APPROVED
Signature: Wayne E. Boss
Date: July 20, 1995
PA 345 of 1970

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 DNR Mon Fd

- 5. Fd 9" B. Cherry N65°E, 12.9
6. Fd 5" Maple S30°E, 42.8
7. Fd 4" Maple S80°W, 31.9
8. Set Spk 22" Tri-Birch N10°W, 9.5

And is accepted as a careful and faithful re-establishment of the position of the original corner.



Signed by [Signature] Date July 28, 1995

Surveyor's Michigan License No. 20703 Lib: # 002 Aut: 389