

**SURVEY &
RECORD DOCUMENTATION**

OCT 18 1996

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX

96 SEP 27 PM 3:27

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. ...
REGISTER OF DEEDS

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey | T <u>32</u> N R <u>5</u> W | <u>G-13</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling
in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous
Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ARTHUR R. RANGER, in a field survey on 05/04, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 1840 John Mullet set the post and witnessed: Beech 12" N79 W 31 lks;
1840 Beech 8" N43 E 34 lks.
1906- E. A. Robinson, surveyor dug a pit and set the stake 4-1/2"x4-1/2", witnessed:
Hemlock 12" S63.5 W 23.5 lks; Mr. Shafer promises to put an old well point deep
in the ground.(see old notes); E.A.R. found the original post prior to setting a new on
1971- Carl Roser, surveyor found 1-1/4" pipe with cap; Pipe fits old witnesses as noted in
old county surveyor's book c-300 dated June 1906 and book c-302.
See LCRC Liber 1, pg. 66. Roser Witnesses: 12" Y. Birch S76 E 9.8'; 16" Y. Birch
S53 W 32.3'; 16" Y. Birch N25 W 50.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13 Arthur R. Ranger, surveyor found the old well point as found by Roser, and to be set per Mr. Shafer in the old notes. Refer to the old surveyor notes. Also found the 1/8th corner to the North set by E. A. Robinson, and mentioned in the old notes. Bearings to the North and West as well as distances to the other corners seemed reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 Found Old Well Point
13" Y. Birch N32 E 4.81'
9" Y. Birch S73 E 19.67'
14" Beech S22 E 38.86'
14" Y. Birch S60 W 32.83'

Charlevoix Co. Surveyor
APPROVED

Signature Mary C. Ferris
Date: July 25, 1996



The old well point is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Arthur R. Ranger
Surveyor's Michigan License No. 31601

Date 05/24/96