

SURVEY & RECORDATION

LIBER 002 Sub 376

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

95 JUN 29 AM 10: 09

SEP 18 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charles M. Peabody
REGISTER OF DEEDS

COMMISSION

For corners in
Charlevoix
(County)

Located In: Corner Code #:

1. Public Land Survey	T	<u>32N</u>	R	<u>5W</u>	<u>H-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Arthur R. Ranger, in a field survey on Nov. 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840- John Mullet, Surveyor set Qr. Section Post and witnessed: Sugar 24" N55°W 381ks; Beech 8" N68°E 51ks.
- 1904- E.A. Robinson, Surveyor used stake in a Section Sub. of 34. Witnesses: Lynn 8" S88°W 27.751ks; Hemlock 36" N18°E 511ks.
- 1971- Carl Roser, Surveyor recovered stake bottom and part of upper stake from old witness SW & NE as noted in old County Surveyor's Book C-302 at Charlevoix County Register of Deeds. Set new witnesses: Set D.N.R. monument by found stake bottom; 8" Ironwood N87°W 32.8'; 9" Maple S31°E 18.9'; 10" Maple N62°E 23.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994- Arthur R. Ranger, Surveyor found D.N.R. monument set by Roser, also found evidence of old County Surveyor witness stumps found by Roser. Stumps were rotten and at ground level. No evidence of occupation. Corner was accepted as found.

Accepted by Surveyor:
APPROVED
Signature *Mary C. Ferritt*
Date June 16, 1995
PA. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13 Found D.N.R. monument set by Roser
- 8" Maple N5°E 2.71'
- 13" Maple N64°E 23.31'
- 9" Maple S28°E 18.87'
- 10" Ironwood S88°W 32.72'

Found DNR monument as recorded in L.1, Pg. 66, Charlevoix County, MI, and is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by *Arthur R. Ranger* Date 06/16/95
Surveyor's Michigan License No. 31601