

SURVEY & RE-MONUMENTATION

SEP 12 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

95 AUG -4 AM 9:24

Charles M. Coakley
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Charlevoix
(County)

Located in:

Corner Code #

- 1. Public Land Survey
- 2. Property Controlling In Section
- 3. Miscellaneous Property in Sec.

T 32N R 5W
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

J-1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne E. Boss, in a field survey on May 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Cedar 12 qr Sec cor (no witnesses) John Mullet 1840
- Set stake in place of Fd down 1/4 tree
- 1. Sugar 18, N140 1/2" W 29 lks. E.K. Robinson, Sep 1883
- Fd 1/4 post
- 2. B. Ash N 30 1/2" E 41 lks E.A. Robinson, Feb 1906
- 1/4 post Fd on E side culver
- 2. (Stump) B. Ash 12, N 30 1/2 E 27' E.A. Robinson, Sep 1924
- Set Iron Pin 7/8" x 18" to re-establish cor according to recital as described in LCRC L. 2. Pg 141, Carl Roser, Jan 1982
- 3. 10" Tamarack N60°W, 50.7
- 4. P. Pole S40°W, 46.43
- 5. 7" Cedar N30°W, 30.6
- 6. 18" Culver W 2'
- 7. Set Cedar Post N 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fd 7/8" Iron Rod
- 3. Fd 10" Tamarack N60°W, 50.7
- 4. Fd P. Pole S40°W, 46.43
- 5. Fd 7" Cedar N30°W, 30.6
- 6. Fd 18" Culver W 2'
- 7. Fd Cedar Post N 33'

Charlevoix Co. Surveyor
APPROVED
 Signature Mary C. Feenelt
 Date: July 20, 1995
 PA 345 of 1996

GLO to I-1 2640 EA Robinson - 2618.9 Roser 2628.54
 GLO to K-1 2640 EA Robinson - 2626 Roser 2628.53

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-1 Charlevoix County Mon Set
- 3. Fd 10" Tamarack N60°W, 50.7
- 4. Fd P. Pole S40°W, 46.43
- 5. 7" Cedar N30°W, 30.6
- 6. 18" Culver W 2'
- 7. Fd Cedar Post N 33'

And is accepted as a careful and faithful re-establishment of the position of the original corner.



signed by *Wayne E. Boss*
 Surveyor's Michigan License No. 20703

Date July 28, 1995

LIB# 002 TAB: 392