

PROPERTY & RECORDATION

SEP 1 3 1995

COMMISSION

LIB: P 002 PAGE 377

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

95 JUN 29 AM 10:11

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

*Charles M. Peaker*  
REGISTER OF DEEDS

For corners in  
Charlevoix  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 32N R 5W L-13  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property In Sec. S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Arthur R. Ranger, in a field survey on Nov. 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840- John Mullet, Surveyor set Qr. Sec. post and witnessed: Sugar 14" N82°E 271ks; Ironwood 8" N83°W 311ks.
- 1878- E. K. Robinson, Surveyor found and used corner in a survey and witnessed: Beech 14" S12°E 4.751ks; Ironwood 8" N83°W 311ks.
- 1906- E. A. Robinson, Surveyor did work in section 36.
- 1971- Carl Roser, Surveyor reset corner per standard BLM instructions- (SP) Witnesses: 5" Tw Maple S72°E 18.1'; 7" Tw. Maple S82°W 10.4'; 10" Tw. Maple N7°W 31.3'; Roser set a D.N.R. monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994- Found the D.N.R. monument set by Roser and witnesses; No evidence of occupation was found; Carl's procedure for resetting the corner seemed reasonable. Corner was accepted.

Approved by Surveyor  
APPROVED  
*Signature Mary C. Ferrell*  
Date: June 16, 1995  
P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 Found D.N.R. monument  
Witnesses:  
9" Maple N32°W 27.14'  
10" Maple West 10.02'  
11" Ash S28°W 17.02'  
6" Maple S68°E 17.92'

Found DNR monument as recorded in L.1, Pg. 69, Charlevoix County, MI, and is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by *Arthur R. Ranger* Date 01/26/95  
Surveyor's Michigan License No. 31601