

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Charlevoix</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>5W</u>	<u>I-8</u>
	T <u>32N</u> R <u>5W</u>	<u>J-8</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Num**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on Apr. 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22	●	23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- |     |  |     |  |
|-----|--|-----|--|
| I-8 | GLO set section post - William Burt, 1850.<br>Wit: Sugar 6" N 20° W 14 links<br>Sugar 14" S 11° E 28 links | J-8 | This position was not established during the original government survey. |
|-----|--|-----|--|

E.A. Robinson, Dec. 1919 tied to this corner while setting the center of Section 23. No new witnesses were recorded.


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- |     |   |     |   |
|-----|---|-----|---|
| I-8 | Set a standard DNR monument at an old fence corner. This position fits well with E.A. Robinson's work done in Section 23. | J-8 | Set a standard DNR monument at an old fence corner. I believe this position is the center of Section 23 set by E.A. Robinson during a Dec. 1919 survey. |
|-----|---|-----|---|

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |     |  |     |   |
|-----|--|-----|---|
| I-8 | Set standard DNR monument.<br>Wit: Set nail in 6" Ironwood S 26° W 15.59'<br>Set nail in 22" Basswood S 70° E 18.51'<br>Set nail in 10" Basswood N 33° W 43.34'<br>Set nail in 6" Maple S 89° W 12.53' | J-8 | Set standard DNR monument.<br>Wit: Set nail in 12" Maple N 14° E 27.86'<br>Set nail in 7" Maple S 89° E 18.79'<br>Set nail in 10" Maple S 21° W 13.67'<br>Set nail in 16" Maple N 72° W 45.79'<br>Old fence running north-south and east-west |
|-----|--|-----|---|

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981



Date 7-26-99