

SURVEY & REMONUMENTATION

JAN 26 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 DEC 15 PM 2:45

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Charlevoix
(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 7W

A-7

T R

T 32N R 8W

M-7

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Charles M. Probert
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Wayne E. Boss

May 97

in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-7 OCTOBER 1856

E.D. ATWATER, DEPUTY SURVEYOR

JUNE 25, 1987

ABOUT 1993

SET POST

BERYL M. JONES

GEORGE J. AVENDT

1. SUGAR 7 INCH N77 1/2W 24 LKS

FD. 1/2" IR

FOUND 1/2" IR WITH CAP 23514

2. SUGAR 9 INCH S60 1/2 W 42 LKS

3. 6" ELM S38E 124.00'

4. 8" POPLAR S10E 60.46'

4. 8" POPLAR S10E 60.53'

5. 7" POPLAR S50E 57.37'

5. 8" POPLAR S57E 57.48'

7. 4" ELM N30E 82.09'

6. 1/2" IR N45W 40.03'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 MAY 1997

FOUND 1/2" IR WITH CAP 23514

4. 8" POPLAR S10E 60.46'

5. 7" POPLAR S50E 57.37' FD. NAIL & TAG

7. 4" ELM N30E 82.09' FD. NAIL

Charlevoix Co. Surveyor

APPROVED

Signature *May C. Reundt*

Date: 12-23-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 1/2 INCH IRON REPLACED WITH CHARLEVOIX COUNTY CONCRETE MONUMENT

4. 8 POPLAR S10E 60.47'

5. 7" POPLAR S50E 57.37'

7. 5" ELM N35E 81.85' SET SPIKE & TAG

8. 5" POPLAR S50E 21.12 SET SPIKE & TAG

9. TWN 4" POPLAR N85E 39.75' SET SPIKE & TAG

10. EAST POST OF SIGN WEST 118.5' SET SPIKE & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by _____

Date 12/12/97

Surveyor's Michigan License No. 20703

LIBER 003 PAGE 128