

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED

98 SEP 15 AM 10:07

Charles M. Barber
REGISTER OF DEEDS

For corners in

<u>Charlevoix</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32</u> N R <u>7</u> W	<u>A-10</u>
	T <u> </u> R <u> </u>	
	T <u>32</u> N R <u>8</u> W	<u>M-10 ANTRIM</u>
	T <u> </u> R <u> </u>	
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property In Sec.	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Wayne E. Boss AUGUST 98
I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-------------------------------|--------------------------|
| A-10 OCTOBER 1856 | MAY 23, 1978 |
| E.D. ATWATER, DEPUTY SURVEYOR | LAWRENCE R. FEINDT |
| SET BEECH POST 3 INCH | SET 3/4 INCH PIPE |
| 1) BEECH 9 INCH N71*W 10 LKS. | 3) 5" BEECH S15*E 10.6' |
| 2) BEECH 6 INCH S20*E 25 LKS. | 4) 5" MAPLE EAST 12.35' |
| | 5) 20" MAPLE N30*W 22.3' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-10 AUGUST 4, 1998
FOUND 1" O.D. PIPE
3) 5" BEECH S34*E 1062' FOUND NAIL
4) 10" MAPLE N85*E 12.35' NAIL GROWN OVER
5) 24" MAPLE N30*W 22.3' NAIL GROWN OVER
A-10 TO A-11 GLO 40 CHAINS (2640.0') MEASURES 2660.02'
A-10 TO A-9 GLO 40 CHAINS (2640.0') MEASURES 2616.26'

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Feindt*
Date: *Aug. 27, 1998*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10 PLACED STEEL CHARLEVOIX COUNTY MARKER
3) 5" BEECH S34*E 10.62' USED NAIL
4) 10" MAPLE N85*E 12.44 SET NAIL & TAG
5) 24" MAPLE N35*W 22.18' SET NAIL & TAG
6) 9" MAPLE S27*W 10.92' SET NAIL & TAG
AND IS ACCEPTED AS A CAREFUL & FAITHFUL RESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*
Surveyor's Michigan License No. 20703

Date *Aug 27, 1998*

