

OCT 19 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED

98 SEP 15 AM 10:01

*Charles M. Coblenz*  
REGISTER OF DEEDS

For corners in

Charlevoix (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 7W	A-11
	T 32N R 8W	M-11 ANTRIM
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Wayne E. Boss

AUGUST 98

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |      |                               |                                   |
|------|-------------------------------|-----------------------------------|
| A-11 | OCTOBER 1856                  | MAY 23, 1978                      |
|      | E.D. ATWATER, DEPUTY SURVEYOR | LAWRENCE R. FEINDT                |
|      | SET BEECH POST 4 INCH         | FOUND 3/4 INCH PIPE UNKNOWN ORGIN |
|      | 1) SUGAR 12" N72W 58 LKS.     | 3) POWER POLE N70E 43.08'         |
|      | 2) BEECH 12" S50 3/4W 26 LKS  | 4) 5" POPLAR S40E 59.88'          |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-11 FOUND 1" OUTSIDE DIAMETER PIPE  
3) POWER POLE N70°E 42.1' FOUND NAIL & CAP IN S.W. FACE CENTER LINE OF TWO TRACK ROAD TO WEST NORTH 18' +/- REMAINS OF WOVEN WIRE FENCE TO SOUTH  
A-10 TO A-11 GLO 40 CHAINS (2640.0') MEASURES 2616.26'  
A-11 TO A-12 GLO 40 CHAINS (2640.0') MEASURES 2620.30'

Charlevoix Co. Surveyor  
**APPROVED**  
Signature *Mary C. Feindt*  
Date: AUG 27 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11 PLACED STEEL CHARLEVOIX COUNTY MARKER  
3) POWER POLE N84°E 43.07' SET NAIL & TAG  
5) FENCE POST NORTH 13.25' SET NAIL & TAG  
6) 12" MAPLE N62°W 27.89' SET NAIL & TAG  
7) 5" ELM S47°E 86.75' SET NAIL & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL RESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*  
Surveyor's Michigan License No. 20703

Date \_\_\_\_\_

