

SURVEY & REMONUMENTATION

FEB 04 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Charlevoix

Located In:

Corner Code #

1. Public Land Survey

T 32N R 7W A-12 ✓
T 32N R 8W M-12
T R
T R

2. Property Controlling in Section

S T R
S T R
S T R
S T R

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Wayne E. Boss

SEPTEMBER 98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 OCTOBER 1856 ESTIMATED 1993
E.D. ATWATER, DEPUTY SURVEYOR PROBABLE BY GEORGE J. AVENDT
SET BEECH POST 3 INCH FOUND 2 INCH PIPE
1. BEECH 12" N53 1/4E 47 LKS. 3. 13" TWIN MAPLE N0E 7.45'
2. SUGAR 20" S25W 34 LKS. 4. 16" MAPLE S34W 12.95' TAG 3920
5. 5" MAPLE S39E 26.80'
6. 16" MAPLE S62E 20.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-12 SEPTEMBER 1, 1998

FOUND 2" PIPE
ON REMAINS OF NORTH & SOUTH WOVEN FENCE AND REMAINS OF WIRE FENCE TO EAST
3. 13" TWIN BASSWOOD N0*E 7.45' FD. BLAZE FACING CORNER
4. 16" STUMP S34*W 12.95' 3920 CAP FACING CORNER
5. 6" MAPLE S39*E 26.80' FD. BLAZE FACING CORNER
6. 16" MAPLE S62*E 20.95' FD. BLAZE FACING CORNER
SLOPES DOWN TO EAST AND WOODED, LARGE TREES RECENTLY HARVESTED TO WEST SEMI OPEN
A-11 TO A-12 GLO 40 CHAINS (2640.0"0 MEASURES 2620.30'
A-12 TO A-13 GLO 40 CHAINS (2640.0;) MEASURES 2620.08'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 PLACED STEEL CHARLEVOIX COUNTY MARKER
3. TWIN 13" BASSWOOD N0*E 7.97' SET NAIL
5. 16" MAPLE S63*E 21.98' SET NAIL & TAG
6. 6" MAPLE S33*E 27.30' SET NAIL & TAG
7. 12" MAPLE S28*W 20.98' SET NAIL & TAG
AND IS ACCEPTED AS A CAREFUL & FAITHFUL RESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by Wayne E. Boss
Surveyor's Michigan License No. 20703

Date Sept. 17, 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECORDED

98 SEP 17 PM 12:37

Charlevoix Co. Surveyors
REGISTERED MAIL LOGS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Charlevoix Co. Surveyors
APPROVED
Signature Mary C. Fiedler
Date: Sept 17, 1998

