

**SURVEY & REMONUMENTATION**

**OCT 19 1998**

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED

98 SEP 15 AM 10:02

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Charlene M. Coakley*  
REGISTER OF DEEDS

For corners in

Charlevoix

(County)

Located In:

Corner Code #

- |                                    |   |                   |
|------------------------------------|---|-------------------|
| 1. Public Land Survey              | T <u>32NR</u> <u>7W</u>                   | <u>B-13</u>       |
|                                    | T <u>    </u> <u>    </u>                 | <u>    </u>       |
|                                    | T <u>31NR</u> <u>7W</u>                   | <u>B-1 ANTRIM</u> |
|                                    | T <u>    </u> <u>    </u>                 | <u>    </u>       |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>       |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>       |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>       |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**Wayne E. Boss**, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**B-13 OCTOBER 24, 1856**  
**EDWARD D. ATWATER, DEPUTY SURVEYOR**  
**SET POST, NO OLD LINE FOUND OR 1/4 CORNER FOUND**  
(1) SUGAR 12 INCH N53 3/4\*W 28 LINKS  
(2) HEMLOCK 24INCH S39 3/4\*W 31 LINKS  
**JUNE 23, 1988 NICHOLAS B. DEYOUNG**  
**FOUND 3/4" IRON PIPE, (3) 7"W.ASH N15\*W 13.58'**  
**(4) 6"MAPLE S47\*E 13.06', (5) 6" BASSWOOD S75\*W18.60'**  
**(6) 6" RED PINE N43\*E 74.15'**

**MAY 20, 1976 MARY C. FEINDT, P.S.**  
**SET IRON PIPE**  
(3) 7" WHITE ASH N15\*W 13.58'  
(4) 6" MAPLE S47\*E 13.06  
(5) 6" BASWOOD S75\*W 18.60'  
**AUGUST 14, 1995 ARTHUR LENNOX**  
**FOUND IRON, (3) 7" W.ASH N13\*W 13.58'**  
**(4) 6" MAPLE S47\*E 13.06'**  
**(5) 8" BASSWOOD S75\*W 19.90'**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**B-13 FEB. 20, 1998**  
**FOUND 1" PIPE IN CONCRETE BOX IN CENTER LINE OF EAST WEST TRAIL**  
(5) 7" BASSWOOD S83\*W 18.71 FOUND BLAZE  
(3) 9" WHITE ASH N9\*W 13.83" FOUND BLAZE  
(8) 6" POPLAR S28\*E 13.43" FOUND BLAZE  
**NO OLD CORNER EVIDENCE WAS FOUND**  
**A-13 TO B-13 GLO 52.12 CHAINS (3439.92') MEASURES 3394.35'**  
**B-13 TO MC WEST OF LAKE GLO 23.72 CHAINS (1565.52') MEASURES 1493.03'**

**Charlevoix Co. Surveyor**  
**APPROVED**  
Signature Mary C. Feindt  
Date: Aug 13, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**B-13 PLACED STEEL CHARLEVOIX COUNTY MARKER APRIL 22, 1998**  
(5) 7" BASSWOOD S83\*W 18.71' SET NAIL & TAG  
(3) 9" WHITE ASH S9\*W 13.83' SET NAIL & TAG  
(8) 6" POPLAR S28\*E 13.43' SET NAIL & TAG  
(9) 4" SUGAR MAPLE N74\*E 20.27' SET NAIL & TAG



AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*  
Surveyor's Michigan License No. 20703

Date Aug. 24, 1998