

SURVEY & REMONUMENTATION

OCT 19 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTER OF DEEDS

98 SEP -8 PM 2:07

Charlevoix Co. Surveyor
REGISTER OF DEEDS

For corners in **SECTION**

<u>Charlevoix</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T2N R 7W</u>	<u>E-13</u>
	<u>T R</u>	
	<u>T1N R 7W</u>	<u>E-1 ASTRIM</u>
	<u>T R</u>	
2. Property Controlling in Section	<u>S T R</u>	
	<u>S T R</u>	
3. Miscellaneous Property in Sec.	<u>S T R</u>	
	<u>S T R</u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne E. Boss, in a field survey on June 98, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-13
- | | |
|--|---|
| OCTOBER 1856
EDWARD D. ATWATER, DEPUTY SURVEYOR
SET CORNER POST, NO OLD CORNER FOUND
1) BEECH 14 INCH N61°E 25 LINKS
2) SUGAR 14 INCH N23°W 36 LINKS
MAY 7, 1984, NICHOLAS B. DEYOUNG
FD.1" SPIKE, 3) SIGN POST S5°W 8.5', 4) POWER POLE S50°W 125.1'
5) 5" ELM S3°W 84.5'. 6) S.END OF CULVERT S50°E 44.4' | JAN. 24, 1997 JAMES E. EVANS, P.S.
FOUND LARGE SPIKE 8' SOUTH OF CENTER LINE
5) 10" BOXELDER STUMP S05°W 85.25'
4) POWER POLE S42°W 125.30' NAIL E. FACE
7) 5" CHERRY N27°E 53.04'
8) YIELD SIGN POST N24°W 64.19' |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13
- FEB. 20, 1998
FOUND LARGE NAIL IN ROAD
ROAD CENTER LINE NORTH 8'
5) 10" BOXELDER STUMP S05°W 85.25'
4) POWER POLE S42°W 125.30' NAIL E. FACE
7) 5" CHERRY N27°E 53.04'
8) YIELD SIGN POST N24°W 64.19'
3) SIGN POST S5°W 8.5'
F-13 TO E-13 GLO 40 CHAINS (2640.0') MEASURES 2628.00'
E-13 TO D-13 GLO 40 CHAINS (2640.0') MEASURES 2627.77'

Charlevoix Co. Surveyor
APPROVED
Signature *Mary E. Feinelt*
Date: Aug 13, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- E-13
- APRIL 22, 1998
PLACED STEEL CHARLEVOIX COUNTY MARKER
ROAD CENTER LINE NORTH 8.0'
5) 10" BOXELDER STUMP S05°W 85.25'
4) POWER POLE S42°W 125.30' NAIL E. FACE
7) 5" CHERRY N27°E 53.04'
8) YIELD SIGN SIGN POST N24°W 64.19'
3) SIGN POST S5°W 8.5'



AND IS ACCEPTED A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*
Surveyor's Michigan License No. 20703

Date Aug. 29, 1998